

TECHNICAL EXHIBIT 2  
**EQUIPMENT INSPECTION**

GENERAL

1. SCOPE:

- a. This specification covers the general requirements for elevator inspection.

2. APPLICABLE PUBLICATIONS: Refer to American National Standards Institute (ANSI), American Society for Testing and Materials (ASTM), American Welding Society, Inc. (AWS), National Electrical Manufacturers Association (NEMA), Industrial Controls and Systems (ICS), National Fire Protection Association (NFPA) and the National Electrical Code (NEC).

3. QUALIFICATION OF CONTRACTOR: The Contractor shall be regularly engaged in elevator inspection services of the general type indicated for inspection herein, and shall have full service facilities to inspect the equipment under this contract. The Contractor shall furnish a list of personnel and their qualifications to the Contracting Officer and the Contracting Officer's Representative prior to performance of any work.

4. INSPECTIONS AND TESTS:

- a. General: Elevators, wheelchair/stairlifts shall be inspected and tested as prescribed by, and in compliance with the latest National, State and local Fire, Safety, Health and Electrical codes.

(1) The Contractor shall notify the Contracting Officer's Representative seventy-two (72) hours prior to performing non-emergency inspections, testing. Contractor shall describe building location and time of inspection. Upon completion of each inspection, inspection reports shall be made by the inspector, listing the equipment serial number, materials used, and any recommendations regarding the equipment. Any equipment operating deficiencies or recommended repair(s) considered to be beyond the scope of this contract shall be specifically listed and described. The contractor shall supply three (3) copies of the inspection report, within two working days after the inspection, the first set to remain with the equipment, the second set is for the Contracting Officer and the last set is for the Contracting Officer's Representative.

(2) Safety Inspection: Equipment covered by this contract is subject to periodic safety and preventive maintenance inspections which may be made by Government personnel or others duly authorized by the Contracting Officer. The Contractor will be notified in advance of such inspections, and will be expected to have a representative present during the inspection. Such inspections, in addition to examining the safety characteristics of the equipment, are to ascertain whether the holder of this contract is performing the required work in accordance with the contract. Deficiencies noted at these inspections are to be corrected by the Contractor at no additional cost to the Government, and any such corrective work shall commence within twenty-four (24) working hours after receipt of written notice from the Contracting Officer.

5. SERVICE INTERRUPTION DURING INSPECTION AND TESTING: Equipment under this contract may be removed from service for a period of not more than four (4) hours to permit inspection and testing. If additional time is needed, the Contractor shall contact the Contracting Officer's Representative and request a time extension.

6. INSPECTION RESULTS:

- a. Service Interruption: In the event inspection or test reveals a defect that makes operation of the equipment dangerous, until repairs are made, the equipment shall be taken out of service, and the Contracting Officer and the Contracting Officer's Representative notified immediately in writing, stating the reason why the equipment should not be in operation.

(End of Technical Exhibit 2)